

Airflow Engineering (SI) Ltd

DIY INSTALLATION INSTRUCTIONS

Ensure fan is switched off
Remove duct tape and remove the ducting section from the fan unit
Remove old box filter
Insert new filter, the arrows show the direction to insert the filter

Insert new filter, the arrows show the direction to insert the filter Replace the ducting section to fan unit, ensuring filter is a tight fit Re-tape ducting section onto fan unit

TURNING OFF FILTER CHANGE LIGHT

GENERATION 1 - OPTION #1

Switch off at the control panel.

Press the "down" button for 8 seconds.

It will beep after about 3 seconds,

but keep it pressed down for the full 8 seconds

02 is displayed in the roof, 20 is displayed in the house.

Press the "on/off" button, and a 1 or a 5 will be displayed.

Press the "on/off" button again, & again to cycle through the numbers displayed until you come back to the 1 or 5 being displayed again.

Press the "function" button to confirm.

GENERATION 1 - OPTION #2

Switch off at the control panel.

Press the "down" button for 8 seconds.

It will beep after about 3 seconds,
but keep it pressed down for the full 8 seconds

02 is displayed in the roof.

Press the "up" button to increase 02 to 22

(not holding it down, just short pushes) Below the 22 you will see a 0

Press the "power" button to increase the 0 to 9

Push the "function" button to save settings.